

ROOM FINISH SCHEDULE

	COLOR SCHEME	FLOOR	BASE	WALLS				CEILING			
			4" PVC VINYL WALL BASE MOLDING	5/8" TYPE X GYPSUM BOARD (TO BE PAINTED)	1/2" GOLD BOND PURPLE XP MOLD & MOISTURE RESISTANT DRYWALL (TO BE PAINTED)	FIBERGLASS REINFORCED PANELS (FRP)	26G METAL SIDE WALL PANEL (PRE-PAINTED)	5/8" TYPE X GYPSUM BOARD (TO BE PAINTED)	1/2" GOLD BOND PURPLE XP MOLD & MOISTURE RESISTANT DRYWALL (TO BE PAINTED)	FIBERGLASS REINFORCED PANELS (FRP)	26G METAL PANEL (PRE-PAINTED)
BLDG. PART "A" ROOMS			HEIGHT	HEIGHT	HEIGHT	HEIGHT					
LOFT	BY OWNER	23X32" PLYWOOD (TO BE PAINTED)	NONE	NONE	NONE	NONE	FLOOR TO CEILING	NONE	NONE	NONE	THROUGHOUT
GARAGE AREA	BY OWNER	CONCRETE WITH SLIP RESISTANT FINISH	NONE	NONE **NOTE	NONE	NONE **NOTE	FLOOR TO CEILING	NONE	NONE	NONE	THROUGHOUT
LOCKER ROOM	BY OWNER		THROUGHOUT	FLOOR TO CEILING	NONE	*4'-0"	NONE	THROUGHOUT	NONE	NONE	NONE
MEN'S RESTROOM	BY OWNER		THROUGHOUT	NONE	FLOOR TO CEILING	4'-0"	NONE	NONE	THROUGHOUT	NONE	NONE
MEN'S SHOWER	BY OWNER		THROUGHOUT	NONE	FLOOR TO CEILING	FLOOR TO CEILING	NONE	NONE	THROUGHOUT	THROUGHOUT	NONE
WOMEN'S RESTROOM	BY OWNER		THROUGHOUT	NONE	FLOOR TO CEILING	4'-0"	NONE	NONE	THROUGHOUT	NONE	NONE
WOMEN'S SHOWER	BY OWNER		THROUGHOUT	NONE	FLOOR TO CEILING	FLOOR TO CEILING	NONE	NONE	THROUGHOUT	THROUGHOUT	NONE
JANITOR'S CLOSET	BY OWNER		THROUGHOUT	FLOOR TO CEILING	NONE	4'-0"	NONE	THROUGHOUT	NONE	NONE	NONE
MECHANICAL ROOM	BY OWNER		THROUGHOUT	FLOOR TO CEILING	NONE	4'-0"	NONE	THROUGHOUT	NONE	NONE	NONE
HALLWAY	BY OWNER		THROUGHOUT	FLOOR TO CEILING	NONE	*4'-0"	NONE	THROUGHOUT	NONE	NONE	NONE
BLDG. PART "B" ROOMS											
STORAGE	BY OWNER	THROUGHOUT	FLOOR TO CEILING	NONE	NONE	NONE	THROUGHOUT	NONE	NONE	NONE	
BREEZEWAY	BY OWNER	THROUGHOUT	FLOOR TO CEILING	NONE	NONE	NONE	THROUGHOUT	NONE	NONE	NONE	

*IN LOCKER ROOM & HALLWAY WALLS AND PARTITIONS WITHIN 2 FEET OF SINKS AND FOUNTAIN, SHALL HAVE A FIBERGLASS REINFORCED PANELS, TO A HEIGHT OF NOT LESS THAN 4 FEET ABOVE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS.

**NOTE:
 INTERIOR WALL IN BLDG. PART "A" GARAGE SHALL BE FINISHED WITH 5/8" TYPE X GYPSUM BOARD (PAINTED) WITH 4'-0" OF FRP BOARD AND 4" PVC VINYL BASE MOLDING. BOTH SIDES OF WALL.