

**CITY OF CONNELLSVILLE
FAYETTE COUNTY, PENNSYLVANIA**

**CITY OF CONNELLSVILLE 2026 PAVING PROJECT
PROJECT NO. 25681**

ADDENDUM NUMBER 1

DATE 5/5/26

All Contractors who may be bidding on the work under this Contract shall read and observe this Addendum and any future Addenda.

Every Bidder shall note that while certain requirements in this Addendum may be specifically noted as applying to a particular page, section, and/or plan in the Contract Documents, such changes shall apply also to any other page, section, and/or plan where the change is relevant.

All Contractors who are bidding on this work shall take cognizance of the revisions, changes, additions, or deletions shown in this and future Addenda and shall provide for the same in their Bid. **PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID PROPOSAL.**

Please be advised of the following changes:

In Alternate Bid #1, the limits of paving have been extended another block (~300') to Gibson. Milling of either edge of the road (7') has been added. Pavement Depth now 2".

PLEASE USE UPDATED AND ATTACHED BID FORM.

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID PROPOSAL


PLEASE EMAIL THIS PAGE ONLY TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM TO WIDMER ENGINEERING INC. AT EMAIL vbowman@widmerengineering.com OR FAX TO 724-626-8509.
THANK YOU!

Attached is the documents containing changes for the Bid Proposal and project locations and estimated quantities.

**WIDMER ENGINEERING, INC.
CONTRACTOR**

SIGNATURE

WIDMER ENGINEERING INC.



**Kerry L. Bell, P.E.
Project Manager**

BID PROPOSAL

Contractor's Name _____
 Address _____
 Telephone Number _____
 Fax Number _____
 e-mail _____
 Federal I.D. Number _____
 Date _____

To: City of Connellsville
 110 North Arch Street
 Connellsville, PA 15425

For: City of Connellsville 2026 Paving Project

Council Members:

1. Pursuant to and in compliance with your request inviting proposals for the construction of the above project and having carefully examined the contract documents, prepared by Widmer Engineering Inc., comprised of the drawings; specifications and all other documents bound therewith; together with all addenda or bulletins thereto; and being familiar with the site and the various conditions affecting the work, the undersigned hereby offers to furnish all plant, labor, supervision, materials, supplies, equipment, and other facilities and things necessary or incidental to the work as required by and in strict accordance with the applicable provisions of the plans and specifications, contract documents, and of all addenda or bulletins issued by the Owner for the unit prices named in the following schedule.

BID PROPOSAL

Paving segments of: E. Peach Street, E. Murphy Avenue, E. Apple Street, E. Gibson Avenue, N. Cottage Avenue, E. Fayette Street, N. Prospect Street, and N. Penn Street

| Item No. | Description | Quantity | Unit Price | Total Amount |
|----------|---|----------|------------|--------------|
| 1. | 1" milling and all cleaning, complete in place. | 532 S.Y. | | |
| 2. | Superpave Asphalt, 9.5 mm PG 64-22, Wearing Course, HMA, 0 to 0.3 million ESAL's, SRL-E, to include a 1.5" Wearing Course, complete in place. | 945 Tons | | |

TOTAL BID AMOUNT: \$_____ (Digits)

TOTAL BID AMOUNT IN WORDS:_____

ALTERNATE BID PROPOSAL

Paving segments of: Mountz Street and Johnson Avenue

| Item No. | Description | Quantity | Unit Price | Total Amount |
|----------|---|----------|------------|--------------|
| 1. | Superpave Asphalt, 19.0 mm PG 64-22, Binder Course, 0 to 0.3 million ESAL's, SRL-E, 2" Course, Installed and compacted complete in place. | 45 Tons | | |
| 2. | Superpave Asphalt, 9.5 mm PG 64-22, Wearing Course, HMA, 0 to 0.3 million ESAL's, SRL-E, to include a 2.0" Wearing Course, complete in place. | 250 Tons | | |
| 3. | 1.5" milling and all cleaning of Johnson, complete in place. | 1,089 SY | | |

TOTAL BID AMOUNT: \$ _____ (Digits)

TOTAL BID AMOUNT IN WORDS: _____

2. The total bid amount is to be shown in both words and figures. In case of discrepancy, the amount shown in words will govern.
3. The above prices shall include all labor, materials, bailing, shoring, removal, overhead, profit, insurance, etc., to cover the finished work as specified.
4. The Bidder understands that the Owner reserves the right to reject any or all bids and to waive any informality in the bidding.
5. The Bidder agrees that this bid shall be good and may not be withdrawn for a period of **forty five (45) calendar days** after the scheduled closing time for receiving bids.
6. Upon receipt of written notice of the acceptance of this bid, Bidder will execute the formal Contract dated within ten (10) days and deliver a Surety Bond or Bonds as required by these Specifications. The bid security attached in the sum of _____ 10% _____ (\$ _____) is to become the property of the Owner in the event the Contract and Bonds are not provided within the time above set forth, as liquidated damages for the delay and additional expense to the Owner caused thereby.
7. The Bidder agrees to commence the Contract work upon receipt of a written "Notice to Proceed" from the Owner and to fully complete the project within **ninety (90) consecutive calendar days** thereafter. The Bidder further agrees to pay as liquidated damages, the sum of **\$200.00 for each calendar day** thereafter.
8. The undersigned represents that he is in receipt of the following number of addenda issued by Widmer Engineering Inc. (If no addenda are issued, insert the word "none" in the following space) _____.
9. By submission of this Bid, each Bidder certifies, and in the cause of a joint Bid, each party thereto certifies as to its own organization, that this Bid has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this Bid with any other Bidder or with any competitor.
10. To the extend he deems it necessary or desirable, the Bidder has reviewed the Drawings and Project Manual, visited the proposed building site and made all site, soil and subsurface tests

and independently verified the location of all underground utilities and other structures and obstructions.

11. The Bidder represents that he has had ample opportunity to request clarification from the Owner and the Engineer about any part of the Drawings and Contract Documents which are not entirely clear to him or about which he has any questions or reservations and that, to the extent he has requested clarifications, he has received satisfactory responses.
12. The Bidder has carefully reviewed the Drawings and Contract Documents for the purpose of detecting any inconsistencies between the Drawings and Specifications (or any items included in the Drawings but not in the Specifications, or in the Specifications but not on the Drawings), and, to the extent he has observed any such inconsistencies and/or omissions, he has duly noted them and has had an adequate opportunity to request clarification from the Owner and the Engineer, and he has received a satisfactory response with respect thereto.
13. The bidder is required to submit an experience statement with this Bid.

Respectfully submitted,

(SEAL)

BIDDER

BY: _____
(Signature)

TITLE: _____

CITY OF CONNELLSVILLE
2026 PAVING PROJECT

PROJECT LOCATIONS AND ESTIMATED QUANTITIES

1. Peach Street – From Pittsburgh Street to N Carnegie Avenue. (295' x 23').

7' Edge Milling Along Bank = 78 S.Y.
Property 1" Depth

1.5" of 9.5mm Wearing Course = 75 Tons

2. Murphy Avenue – From Pittsburgh Street to Decatur Street. (170' x 40')

7' Edge Milling – 1" Depth = 264 S.Y.

1.5" of 9.5mm Wearing Course = 75 Tons

3. Apple Street – From Pittsburgh Street to N. Carnegie Avenue. (260' x 24')

Milling 1" Depth (7' Width Along Northern Edge) = 190 SY

1.5" of 9.5mm Wearing Course = 65 Tons

4. Gibson Avenue – Pittsburgh Street to Stone & Company. (260' x 41' or 31, width varies by block)

1.5" of 9.5mm Wearing Course = 100 Tons

5. N. Cottage Avenue – From Fayette Street to Highlands ER on Murphy. (750' x 25')

1.5" of 9.5mm Wearing Course = 195 Tons

6. Fayette Street – From N. Jefferson Street to W. Crawford Avenue (780' x 28')

1.5" of 9.5mm Wearing Course = 230 Tons

CITY OF CONNELLSVILLE
2026 PAVING PROJECT

7. N. Prospect Street – From Francis Avenue to E. Gibson Avenue (305' x 21')

1.5" of 9.5mm Wearing Course = 70 Tons

8. Penn Street – From Francis Avenue to Murphy Avenue. (610' x 21')

1.5" of 9.5mm Wearing Course = 135 Tons

ALTERNATE BID

9. Mountz Street – From West Gibson Avenue to End (150'x20')

2" of 19.0 mm Binder Course = 45 Tons

1.5" of 9.5 mm Wearing Course = 35 Tons

10. Johnson Avenue – From West Fayette Street to West Gibson Avenue (700'x27')

7" Edge Milling – 1" Depth = 1,089 SY

2" of 9.5mm Wearing Course = 250 Tons